



TIME SAVINGS  
**83 HOURS**

LABOUR SAVINGS  
**€ 3,338**

INSTALLATION TIME  
**17 HOURS**

During the construction of a new office building in Altensteig, ventilation ducts were installed on 1,800 square metres using the new Fast Trak fastening system. A total of 500 rails and 1000 beams were used.

### Project Summary

<b>Building type</b>	Office building
<b>Completion date</b>	March 2022
<b>Building structure</b>	Concrete ceiling
<b>Product suspended</b>	Ventilation duct

### Featured Products



“The installers were thrilled by the **simplicity of the installation** and the time advantage compared to traditional suspension methods. By using Fast Trak a total of 2 weeks working time was saved.”

- Project Manager

### COST SAVING SUMMARY

	GripplE solution	Traditional method
Overview	<b>Fast Trak Standard</b>	Threaded rod, C-rail
Material cost	<b>4 377 €</b>	3 980 €
Installation time	<b>17 hours</b>	100 hours
Labour rate (per hour)	<b>45 €</b>	45 €
Total labour cost	<b>765 €</b>	4 500 €
Total cost	<b>5 142 €</b>	8 480 €